

MF2H03

METAMAT FLOOR TO FLOOR

2 HOUR RATED FIRE BARRIER SYSTEM

UL LISTINGS: FF-D-0060, FF-D-0061, FF-D-0064

MAX OPEN = 3" (76mm)

PATENTS PENDING

APPLICATION:

FOR USE WITH BALCO 7500 SERIES FLOOR
COVERS WITH ANCHORS AT 20" (508mm) O.C.
AND EPDM COVERS WITH ANCHORS AT 10"
(254mm) O.C.


NOTES:

FIRE RATING IS DETERMINED NOT ONLY BY
THE METAMAT FIRE BARRIER, BUT ALSO BY
THE PERFORMANCE CAPABILITIES OF THE
SURROUNDING CONSTRUCTION

LENGTHS:

AVAILABLE IN 20FT AND 40FT ROLLS

PLEASE SPECIFY: _____




Project:	
Customer:	
SO#	
Date:	
Page ____ of ____	Scale: NTS

Length	Qty.	Color

Drawn By: JMH

The information contained herein is the proprietary property of **BALCO, INC.** No portion of it may be reproduced by any means or used in any form except for the purpose for which it was furnished. All rights of design and invention are hereby reserved.



BALCO INC

2626 S. Sheridan PO Box 17249
Wichita, Kansas 67217-0249 USA
P: +1-316-945-9328 F: +1-316-945-0789