


MODEL	Width	Depth
BCSF-SL-050	1/2" (13mm)	1 1/2" (38mm)
BCSF-SL-062	5/8" (16mm)	1 1/2" (38mm)
BCSF-SL-075	3/4" (19mm)	1 1/2" (38mm)
BCSF-SL-100	1" (25mm)	2" (51mm)
BCSF-SL-125	1 1/4" (32mm)	2" (51mm)
BCSF-SL-150	1 1/2" (38mm)	2" (51mm)
BCSF-SL-175	1 3/4" (44mm)	2" (51mm)
BCSF-SL-200	2" (51mm)	3" (76mm)
BCSF-SL-225	2 1/4" (57mm)	3" (76mm)
BCSF-SL-250	2 1/2" (64mm)	3" (76mm)
BCSF-SL-275	2 3/4" (70mm)	3" (76mm)
BCSF-SL-300	3" (76mm)	3" (76mm)
BCSF-SL-325	3 1/4" (83mm)	3" (76mm)
BCSF-SL-350	3 1/2" (89mm)	3" (76mm)
BCSF-SL-375	3 3/4" (95mm)	4" (102mm)
BCSF-SL-400	4" (102mm)	4" (102mm)
BCSF-SL-500	5" (127mm)	4" (102mm)
BCSF-SL-600	6" (152mm)	4" (102mm)

BCSF-SL SERIES

COMPRESSED FLOOR SEAL
WITH TRAFFIC GRADE SILICONE FACING
50% MOVEMENT
AVAILABLE IN 5'-0" (1524mm) PIECES

NOTE: METAL COVER REQUIRED
AT PEDESTRIAN TRAFFIC.

COLOR: AVAILABLE IN GRAY ONLY



Project:	
Customer:	
SO#	
Date:	
Page ____ of ____	Scale: NTS

Length	Qty.	Color

Drawn By: RJT

The information contained herein is the proprietary property of **BALCO, INC.** No portion of it may be reproduced by any means or used in any form except for the purpose for which it was furnished. All rights of design and invention are hereby reserved.



2626 S. Sheridan PO Box 17249
Wichita, Kansas 67217-0249 USA
P: +1-316-945-9328 F: +1-316-945-0789

REV. - 5/19/08